

TWO DUCT TYPICAL ARRANGEMENT ENCASED IN CONCRETE DIAGRAM B4-4 DETAIL 2

TELEPHONE DUCT BANKS DETAIL (TYP.)


NOTE:
 PROVIDE LABELS AND PULL STRINGS FOR ALL CONDUITS
 EXACT CONDUIT RUNS INDICATED TO BE VERIFIED ON SITE

NOTES:
 STARBUCKS G.C. IS RESPONSIBLE FOR PROVIDING ALL BOLLARDS, FOOTINGS AND UNDER GRADE CONDUITS FOR DRIVE-THRU SIGNAGE.
 COORDINATE WITH STARBUCKS CONSTRUCTION MANAGER ALL WORK.
 SHELL BUILDING G.C. TO COORDINATE WITH STARBUCKS AND SITE SERVICES G.C. ALL FOUNDATION REQUIREMENTS FOR SIGNAGE PRIOR TO PLACEMENT OF ANY CONCRETE
 CONTACT INSPECTOR FOR SIGN FOOTING INSPECTION PRIOR TO POURING CONCRETE.

REVISIONS

NO.	DATE	DESCRIPTION
1		
2		
3		
2		
1	APR 2023	ISSUED FOR SPA
NO.	DATE	TO

ISSUED



DESIGNER:
 GAC ENGINEERING SERVICES INC.
 1080 TAPS-COTT RD UNIT 18
 TORONTO, ON M1X 1E7
 OFFICE No. - (416) 292-0527
 CELL No. - (416) 710-8274
 gac_engineering@yahoo.ca



DRAWING NOTES:
 1. THE GENERAL CONTRACTOR SHALL CHECK AND VERIFY DIMENSIONS ON SITE AND REPORT ERRORS AND OMISSIONS
 2. DRAWINGS MUST NOT BE SCALED. DRAWINGS ARE DIAGRAMMATIC CONCEPT OF THE DESIGN.
 3. CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR CONSISTENCY WITH THE INTENT OF THE DRAWINGS AND SPECIFICATIONS.

CLIENT:

PROJECT TITLE:
 PROPOSED PHASE 3
 DEVELOPMENT - BUILDING C
 9281 COUNTY RD. 93
 TOWN OF MIDLAND, ONTARIO

DRAWING TITLE:
 ELECTRICAL SITE PLAN

DRAWN BY:
 A. C.

CHECKED BY:
 G. C.

SCALE:
 3/32" = 1'-0"

DATE:
 APRIL 2023

PROJECT NO.:
 023023

E-1

PHASE 3 SCOPE OF WORK:

LEGEND
 (2) PHASE 2
 (3) PHASE 3

PHASE 3 LIST OF WORKS:
 - UPGRADE EXISTING SITE TRANSFORMER TO 500KVA (INSTALLATION BY NIT POWER)
 - PROPOSED SEPARATELY METERED 200A, 600V, 3PH ELECTRICAL SERVICE TO BUILDING C
 - PROPOSED DATA + PHONE CABLE SERVICE TO BUILDING C